PASHUPATASTRA — RAILWAY OPERATIONS AI

Railway Domain & Data Foundation

Complete Engineering Specification, 7-Feature ML Scoring Architecture, 5 Disruption Models & Master Golden Scenario

AUTHOR / LEAD

Darshini (Domain & Data Lead)

Branch: `feature/domain-data`

TARGET CONSUMERS

Ayush (ML), Tyagi (Optimizer), Mehta (API), Archit (UI), Tirth (Recovery), Aryan (Lead)

CORRIDOR TESTBED

CORR-NDLS-AGC (New Delhi – Agra Cantt High-Speed Trunk Mainline)

VERIFICATION STATUS

✓ 29 / 29 Automated Checks Passed

Full Contract & Schema Conformance

Indian Railways Operations Context • Track, TRD, S&T Engineering

Document Version 1.0 • August 2026

Executive Summary & Architecture Roadmap

This document provides the canonical railway domain definitions, mathematical scoring data mappings, deterministic disruption specifications, and master benchmark scenarios for **Pashupatastra**. It establishes the operational reality of Indian Railways (IR) across civil (P-Way), electrical (TRD/OHE), and signalling (S&T) engineering departments.

> **Core System Mission**
>
> Seamlessly connect real railway maintenance inspection data into risk/priority scoring, CP-SAT mathematical optimization, real-time disruption handling, and interactive visual explanation.

12	7	5	100%
CANDIDATE BLOCKS	SCORING FEATURES	DISRUPTION SCENARIOS	CONTRACT VALIDATED

System Integration Flow Across Modules

```
                    ┌─────────────────────────────────────────────────────────┐
                    │                 DARSHINI (Domain & Data)                │
                    │  - Multi-Asset Hierarchy  - 7 Scoring Inputs            │
                    │  - Golden Benchmark       - 5 Disruption Payloads       │
                    └────────────────────────────┬────────────────────────────┘
                                                 │
                                                 ▼
                    ┌─────────────────────────────────────────────────────────┐
                    │                   AYUSH (ML & Scoring)                  │
                    │  - ScoringFeatureAdapter  - risk_score / priority_score│
                    └────────────────────────────┬────────────────────────────┘
                                                 │
                                                 ▼
                    ┌─────────────────────────────────────────────────────────┐
                    │                 TYAGI (CP-SAT Optimizer)                │
                    │  - Interval Scheduling     - Committed Locks            │
                    │  - Headway & Dependencies - Mutual Exclusion Groups     │
                    └────────────────────────────┬────────────────────────────┘
                                                 │
                                                 ▼
   ┌─────────────────────────────────────────────┴───────────────────────────────────────────┐
   │                                                                                         │
   ▼                                                                                         ▼
┌──────────────────────────────────┐                                     ┌──────────────────────────────────┐
│       MEHTA (API Backend)        │                                     │   TIRTH (Simulation & Recovery)  │
│  - POST /optimize                │                                     │  - Disruption Injection          │
│  - POST /disrupt                 │                                     │  - Affected Work Identification  │
└────────────────┬─────────────────┘                                     └────────────────┬─────────────────┘
                 │                                                                        │
                 └──────────────────────────────────┬─────────────────────────────────────┘
                                                    │
                                                    ▼
                                   ┌──────────────────────────────────┐
                                   │        ARCHIT (Frontend UI)      │
                                   │  - Before vs After Timelines     │
                                   │  - Explainability Cards & KPIs   │
                                   └──────────────────────────────────┘
```

1. Railway Domain Definitions & Entity Hierarchy

1.1 Core Entities

Entity	Railway Operational Definition	Key Attributes
Corridor `Corridor`	A contiguous operational railway trunk route spanning multiple stations, block sections, and administrative divisions (e.g. *New Delhi – Agra Cantt Section*, 195 km, Northern / North Central Railway).	`corridor_id`, `name`, `zone`, `division`, `tracks`, `assets`
Track `TrackSegment`	A physical directional line along a corridor along which trains operate and on which exclusive maintenance possessions are granted. • **UP:** Towards Zonal HQ / Capital (e.g. \`UP-1\`) • **DOWN:** Away from Zonal HQ (e.g. \`DOWN-1\`)	`track_id`, `corridor_id`, `direction`, `speed_limit_kmh`, `daily_train_density`, `route_classification`
Asset `Asset`	A physical engineering component installed at a specific kilometric location along or over a track (Rail Section, Turnout Point, OHE Mast, Signal Post, Track Circuit).	`asset_id`, `name`, `asset_type`, `track_id`, `km_location`, `criticality`, `condition_score`, `defect_severity`
Maintenance Block `BlockCandidate`	A formal engineering possession request granting exclusive track occupancy to work gangs and machinery while suspending revenue train traffic.	`block_id`, `asset_id`, `track_id`, `work_type`, `duration_minutes`, `priority_score`, `risk_score`
Committed Block `is_committed: true`	A maintenance block already sanctioned and mobilized on site. **Operational Invariant:** The solver must freeze its start time, track, and duration during re-optimization.	`is_committed = True`, `status = "COMMITTED"`
Disruption `DisruptionEvent`	An unplanned real-time disturbance (e.g. rail fracture, OHE wire break, train delay curtailing possession) forcing schedule recalculation.	`disruption_id`, `disruption_type`, `track_id`, `start_minute`, `end_minute`

1.2 Multi-Asset Track Topology & Physical Relationship

Clarification: Can a Single Track Host Multiple Assets? YES.

A single track segment (e.g. `UP-1` between KM 0.0 and KM 50.0) contains hundreds of distinct assets: 50+ Rail Sections (CWR), 12+ Turnouts at yard throats, 700+ OHE Masts every 60–70m, and 25+ Signal Posts.

```
================================ TRACK UP-1 (KM 0.0 to KM 50.0) ================================
KM 0.0          KM 8.5            KM 14.2           KM 24.1           KM 32.0           KM 50.0
 ├─[RAI-001]────[RAI-004]────────[RAI-005]────────[TUR-008]────────[RAI-010]─────────┤  (Civil Rails)
 ├─[OHE-001]────[OHE-002]────────[OHE-003]────────[OHE-004]────────[OHE-006]─────────┤  (25kV OHE Masts)
 ├─[SIG-001]─────────────────────[SIG-002]─────────────────────────[SIG-003]─────────┤  (Signals)
================================================================================================
```

Key Spatial & Scheduling Rules:

- **Track Possession:** Every maintenance task specifies an `asset_id`, but requires exclusive occupancy of its hosting `track_id`.
- **No Overlap:** Two tasks on the same track cannot run concurrently unless they share a certified compound possession window.
- **Headway Buffer:** Minimum 15 minutes safety buffer between sequential blocks on the same track for work-train clearing.
- **Machine Groups:** Shared heavy equipment (e.g., Tie-Tamper `CSM_TAMPER_01`, Tower Wagon `TOWER_WAGON_01`) cannot be scheduled simultaneously anywhere on the corridor.

2. 7-Feature ML Scoring Domain Data Mapping

Ayush's scoring engine requires 7 clean numerical inputs to compute `risk_score` and `priority_score`. Below is the exact operational mapping to Indian Railways data sources and fallback logic:

#	Feature Name	Domain Meaning & Physical Context	Type / Range	Real Indian Railways Source	Demo Fallback / Formula
1	`asset_criticality`	Operational importance of track/asset based on route classification, speed potential, and traffic throughput.	`float` [0.0, 1.0]	**TMS (Track Management System)** Route Classification (Group A = 0.95, Group B = 0.80, Group D = 0.40).	$0.4 \cdot \text{route} + 0.3 \cdot \frac{\text{speed}}{160} + 0.3 \cdot \frac{\text{density}}{120}$
2	`defect_severity`	Severity level of physical flaw detected during recent ultrasound/geometry inspection.	`float` [0.0, 1.0]	**USFD Flaw Registers**, **OMS-2000 (TRC)** acceleration peaks, **OHE Current Collection logs**.	`NONE` = 0.00 `MINOR` = 0.25 `MODERATE` = 0.60 `CRITICAL` = 1.00
3	`days_overdue`	Days elapsed past the statutory maintenance due date prescribed by the IRPWM manual.	`int` ≥ 0 (Norm [0, 1])	**TMS Overhaul Schedule (POH/IOH)** and **TRD Maintenance Ledgers**.	$\min\left(1.0, \frac{\text{days}}{90}\right)$
4	`failure_probability`	Estimated probability of in-service failure within 7 days if maintenance is deferred.	`float` [0.0, 1.0]	**Weibull Degradation Curves** fitted on Gross Million Tonnes (GMT) and condition scores.	$(1.0 - \text{cond}) \cdot 0.5 + 0.4 \cdot \text{sev} + 0.2 \cdot \frac{\text{GMT}}{500}$
5	`train_impact`	Operational delay index caused by blocking track (conflicting passenger and freight trains).	`float` [0.0, 1.0]	**COA (Control Office Application)** & **ICMS Timetable Density**.	$0.5 \cdot \frac{\text{density}}{120} + 0.3 \cdot \frac{\text{dur}}{240} + \text{peak}$
6	`maintenance_duration`	SOP execution duration in minutes including work train setup and safety restoration.	`int` (Minutes) (Norm [0, 1])	**Indian Railways Engineering Code & Standard Time Norms (IRPWM Ch. 5)**.	$\min\left(1.0, \frac{\text{duration}}{360}\right)$
7	`historical_failure_rate`	Frequency of unscheduled breakdowns or weld fractures on this asset/section over past 3 years.	`float` [0.0, 1.0]	**SIMS (Safety Information Management System)** & **Rail Madad Logs**.	$\min\left(1.0, \frac{\text{incidents in 3yr}}{6}\right)$

2.1 Baseline Mathematical Scoring Formulation

```
# Risk Score Formulation (Risk Mitigation Objective) risk_score = 0.30 * defect_severity + 0.30 * failure_probability + 0.20
* days_overdue_norm + 0.20 * historical_failure_rate # Priority Score Formulation (Priority Maximization Objective)
priority_score = 0.35 * risk_score + 0.25 * asset_criticality + 0.20 * train_impact + 0.20 * (1.0 - duration_norm)
```

3. Work Types & 5 Standardized Disruption Scenarios

3.1 Standard Railway Work Types

Work Type	Engineering Scope	Standard Duration	Machinery Group	Precedence Rules
`TRACK_RENEWAL`	Complete Track Renewal (CTR), rails & sleepers.	180 – 360 min	`PQRS_GANG_01`, `BCM_01`	Must precede `BALLAST_TAMPING`
`BALLAST_TAMPING`	Track packing & alignment using Tie-Tampers.	90 – 180 min	`CSM_TAMPER_01`	Requires 15m buffer after renewal
`OHE_MAINTENANCE`	25kV contact wire check & insulator washing.	60 – 150 min	`TOWER_WAGON_01`	Requires Electrical Power Block
`SIGNALLING_INTERLOCKING`	Point machine overhaul & track circuit calibration.	45 – 120 min	`S_T_GANG_01`	Requires approach locking clearance
`ROUTINE_INSPECTION`	USFD rail flaw patrol & track geometry check.	30 – 90 min	None (Manual / Trolley)	Flexible placement
`EMERGENCY_REPAIR`	Rail fracture clamp, weld fix, broken dropper fix.	60 – 180 min	Dynamic Allocation	Pre-empts routine maintenance

3.2 The 5 Standardized Disruption Scenarios (Tirth Integration)

Scenario ID	Trigger & Operational Event	Disruption Payload Summary	Expected Solver & System Action
Scenario 1 `TRACK_UNAVAILABLE`	Track `UP-1` blocked between 01:00 and 04:00 (min 60–240) due to rail defect.	`track_id: "UP-1"` `start_minute: 60`, `end_minute: 240`	Committed blocks remain frozen; non-committed blocks reschedule to afternoon/evening slots or are deferred with reason `TRACK_UNAVAILABLE_IN_WINDOW`.
Scenario 2 `EMERGENCY_WORK`	Urgent rail fracture detected at KM 14.2 on `DOWN-1` requiring 90m block.	`work_type: "EMERGENCY_REPAIR"` `priority: 0.995`, `risk: 0.980`	Solver immediately inserts emergency block in prime night window, displacing lower-priority routine inspections.
Scenario 3 `POSSESSION_CURTAILMENT`	Late running Express train delays midday window on `UP-1` from 180m to 90m.	`window_id: "POS-UP-1-MIDDAY"` Curtailed to [750, 840]	Long tasks exceeding 90m are moved to evening window or deferred; shorter 45m inspections fit into truncated slot.
Scenario 4 `ASSET_CONDITION_DEGRADATION`	Point machine motor resistance alert on `AST-DN1-TUR-012` jumps to CRITICAL.	`affected_asset_id: "AST-DN1-TUR-012"` Priority jumps 0.39 $\to$ 0.94	Feature adapter recalculates risk/priority; solver promotes this candidate from deferred to scheduled status.
Scenario 5 `INFEASIBLE_SCENARIO`	All possession windows revoked while committed blocks are locked in place.	`track_id: "DOWN-1"` Revoked windows with 2 committed locks	Solver gracefully returns status `INFEASIBLE` with structured explanation `COMMITTED_BLOCK_WINDOW_REVOKED` without crash.

4. The Master Golden Scenario (Benchmark Dataset)

The **Golden Scenario** (`golden_scenario.json`) is the master end-to-end benchmark dataset for the team demo on **CORR-NDLS-AGC** (UP-1 & DOWN-1).

4.1 The 12 Candidate Maintenance Blocks

Block ID	Asset ID	Track	Work Type	Dur	Prio	Risk	Machine Group	Initial Outcome	Recovery Outcome
BLK-001	AST-DN1-OHE-001	DOWN-1	OHE_MAINTENANCE	120m	0.820	0.710	TOWER_WAGON_01	SCHEDULED (30–150)	LOCKED (30–150)
BLK-002	AST-DN1-RAI-002	DOWN-1	BALLAST_TAMPING	105m	0.740	0.650	CSM_TAMPER_01	SCHEDULED (165–270)	SCHEDULED (165–270)
BLK-003	AST-UP1-OHE-003	UP-1	OHE_MAINTENANCE	90m	0.880	0.780	TOWER_WAGON_01	SCHEDULED (690–780)	LOCKED (690–780)
BLK-004	AST-UP1-RAI-004	UP-1	BALLAST_TAMPING	90m	0.810	0.690	CSM_TAMPER_01	SCHEDULED (30–120)	MOVED (1260–1350)
BLK-005	AST-UP1-RAI-005	UP-1	TRACK_RENEWAL	150m	0.910	0.840	None	SCHEDULED (135–285)	DEFERRED (Disrupted)
BLK-006	AST-UP1-OHE-006	UP-1	OHE_MAINTENANCE	90m	0.990	0.890	TOWER_WAGON_01	SCHEDULED (1260–1350)	SCHEDULED (1260–1350)
BLK-007	AST-DN1-OHE-007	DOWN-1	OHE_MAINTENANCE	120m	0.850	0.720	TOWER_WAGON_01	SCHEDULED (690–810)	SCHEDULED (690–810)
BLK-008	AST-UP1-RAI-008	UP-1	ROUTINE_INSPECTION	45m	0.310	0.220	None	SCHEDULED (795–840)	SCHEDULED (795–840)
BLK-009	AST-DN1-RAI-009	DOWN-1	BALLAST_TAMPING	120m	0.580	0.510	CSM_TAMPER_01	DEFERRED (Machinery)	DEFERRED
BLK-010	AST-UP1-RAI-010	UP-1	BALLAST_TAMPING	135m	0.520	0.480	CSM_TAMPER_01	DEFERRED (Headway)	DEFERRED
BLK-011	AST-DN1-	DOWN-1	SIGNALLING_INTERLOCKING	90m	0.440	0.380	S_T_GANG_01	DEFERRED (Priority)	DEFERRED

Block ID	Asset ID	Track	Work Type	Dur	Prio	Risk	Machine Group	Initial Outcome	Recovery Outcome
	SIG-011								
BLK-012	AST-DN1-TUR-012	DOWN-1	ROUTINE_INSPECTION	60m	0.390	0.310	None	DEFERRED (Capacity)	DEFERRED

4.2 The 8-Step End-to-End System Demo Journey

```
STEP 1: Raw Inspection Records (Darshini) ────► 12 candidates with 7-feature scoring metadata
                                                        │
STEP 2: Feature Adapter & ML Scoring (Ayush) ───► Calculates risk_score and priority_score
                                                        │
STEP 3: Baseline Optimization (Tyagi) ──────────► 8 Scheduled (Total Priority: 6.31), 4 Deferred
                                                        │
STEP 4: Section Controller Locks Work ──────────► BLK-001 (DOWN-1) and BLK-003 (UP-1) set to is_committed: true
                                                        │
STEP 5: Disruption Injected (Tirth) ────────────► Track UP-1 closed min 60 to 240 (Rail Defect)
                                                        │
STEP 6: Re-Optimization (Tyagi) ────────────────► Committed BLK-003 locked; BLK-004 shifted to evening
                                                        │
STEP 7: API Response Delivery (Mehta) ──────────► POST /optimize & POST /disrupt returning compliant JSON
                                                        │
STEP 8: Dashboard Display (Archit) ─────────────► Before vs After visual timeline comparison with KPI deltas
```

5. Verification & Code Artifacts Directory

5.1 Automated Verification Matrix (29/29 Passed)

Category	Verification Item	Result
Documentation	`DOMAIN_SPECIFICATION.md` exists with all 5 mandatory sections	PASS
Topology	Multi-asset track hierarchy documented and verified	PASS
Scoring Features	All 7 features defined with valid mathematical ranges [0.0, 1.0]	PASS
Domain Models	`models.py`: `Asset`, `TrackSegment`, `Corridor` serialization	PASS
Feature Adapter	`feature_adapter.py` extracts normalized inputs for ML engine	PASS
Golden Fixture	`golden_scenario.json` conforms to `OptimizationRequest` schema	PASS
Disruptions	`disruption_scenarios.json` covers all 5 standardized disruption types	PASS
Committed Invariant	Committed blocks locked in time and track across solver invocations	PASS

5.2 Deliverables Location Index

File	Workspace Location	Description
`DOMAIN_SPECIFICATION.md`	`c:\Users\Hp\Documents\phasupatashtra\DOMAIN_SPECIFICATION.md`	Authoritative railway domain reference specification.
`models.py`	`backend/app/data/models.py`	Enriched dataclass domain models with serialization methods.
`feature_adapter.py`	`backend/app/data/feature_adapter.py`	Domain-to-scoring feature extractor and normalizer.
`golden_scenario.json`	`backend/app/data/fixtures/golden_scenario.json`	Master 12-block end-to-end benchmark dataset.
`disruption_scenarios.json`	`backend/app/data/fixtures/disruption_scenarios.json`	5 standardized disruption test payloads for simulation.

File	Workspace Location	Description
`generator.py`	`backend/app/data/generator.py`	Seed-driven deterministic synthetic scenario generator.
`verify_darshini_deliverables.ps1`	`c:\Users\Hp\Documents\phasupatashtra\verify_darshini_deliverables.ps1`	Automated PowerShell test runner.